

EXTERIOR FINISHES, LLC

RESIDENTIAL | COMMERCIAL

Vendor Pricing Valid 60 Days Unless Noted Otherwise.

Date: 8/6/2025

Homeowner: Robin King

Address: 2109 103rd Ave SE, Lake Stevens, WA 98258

Project Inclusions:

Exterior Finishes have included Material and Labor to replace the entirety of the Lake Stevens Grange Siding.

Complete Removal of Existing Siding

- Full tear-off of all existing siding, corner trims, and related materials.
- Debris removal and proper disposal included.

Inspection of Substrate

- Visual inspection of exposed sheathing once siding is removed.
- Any required substrate repairs will be quoted at a T&M rate of \$125/hr

Weather Barrier Installation

- Installation of code-compliant weather-resistive barrier (WRB) over all wall surfaces.
- Proper taping and sealing around all seams and openings.

Flashing & Waterproofing

- New flashing installed at all windows, doors, and wall penetrations.
- Kick-out flashing and roof-to-wall integration where applicable.

Siding Installation

- Installation of new James Hardie ColorPlus siding (color TBD).
- Final profile and style to be selected by homeowner prior to material order.

Trim Details

- ColorPlus Hardie trim installed at windows, doors, corners, and horizontal transitions.

Caulking and Sealing

- Application of high-quality, color-matched sealant at all necessary joints and transitions.

EXTERIOR FINISHES, LLC

RESIDENTIAL | COMMERCIAL

Vendor Pricing Valid 60 Days Unless Noted Otherwise.

Fasteners & Accessories

- Use of corrosion-resistant fasteners and manufacturer-approved accessories.

Final Clean-Up

- Jobsite cleaned daily, full debris removal and magnetic nail sweep upon completion.

Total Cost to Supply and Install Items Listed W/O WSST: \$46,260.00

Project Specific Options:

Option to Supply and Install Primed Material (Needs Paint):

Exterior Finishes has included an option to supply and install James Hardie 8.25 (7" Reveal).

Total Cost for Primed Option: \$35,466.00

Supply and Installation of Full Painting Scope:

Exterior Finishes has included an option to supply and install 2 coats of Sherwin Williams A-100 paint to the entirety of the building.

Total Cost for Full Property Painting: \$10,794.00

Supply and Installation of Eaves Painting:

Exterior Finishes has included an option to supply and install 2 coats of Sherwin Williams A-100 paint to the eaves. (This option is only needed if the ColorPlus option is selected).

Total Cost for the Eaves Painting Option: \$1,036.00

EXTERIOR FINISHES, LLC

RESIDENTIAL | COMMERCIAL

Vendor Pricing Valid 60 Days Unless Noted Otherwise.

Project Specific Exclusions:

- Gutters
- Fascia
- Roofing

Base Exclusions:

- Special OCIP requirements, prevailing/special wages (unless specified), permits, testing of any kind.
- All exterior insulation and girt systems.
- Cranes, forklift, scaffolding, flaggers, traffic control for material delivery, certified riggers.
- Supply or install of gutters/downspouts.
- Roof scoped work beyond siding including scuppers, venting and coping.
- All work that goes below grade.
- WSST or retentions greater than 5%.

Exterior Finishes Insurance Limits

GL-\$1,000,000, GA-\$2,000,000.00

Umbrella Liability- EO-\$2,000,000, Aggregate \$2,000,000

Copy Of insurance certificate available upon request.

Exterior Finishes would like to thank you for the opportunity to quote your upcoming project. Please do not hesitate to contact us if you have any questions or concerns.

Sincerely,

Anthony Hutchinson